

Syr Hugh Owen School



Description

Extension to existing administration block, new refectory, 11 classroom teaching block and 6 classroom practical block at Sir Hugh Owen School Caernarfon. The works were carried out within the confines of the existing school and required close liaison and coordination with staff to ensure minimal disruption. The structures were of a traditional design. Load-bearing brickwork externally supported pre-cast concrete 1st floors and timber trussed roofs which were covered in local Welsh Perghn Slate.



Client

Gwynedd County Council

Value

£1,700,000

Type of Contract

Private with quantities

Consultants

Engineer: Shepherd Gilmour